

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED **SITE FILE COPY**
DATE ENTEREDSEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS**1 NAME**

HISTORIC

Rocheport

AND/OR COMMON

Rocheport Historic District

2 LOCATION

STREET & NUMBER

CITY, TOWN

Rocheport

VICINITY OF

NOT FOR PUBLICATION

CONGRESSIONAL DISTRICT

#8 - Hon. Richard H. Ichord

STATE

Missouri 65279

CODE 29

COUNTY Boone

CODE 019

3 CLASSIFICATION

CATEGORY

☒ DISTRICT
☐ BUILDING(S)
☐ STRUCTURE
☐ SITE
☐ OBJECT

OWNERSHIP

☐ PUBLIC
☐ PRIVATE
☒ BOTH

PUBLIC ACQUISITION

☐ IN PROCESS
☐ BEING CONSIDERED

STATUS

☒ OCCUPIED
☐ UNOCCUPIED
☐ WORK IN PROGRESS
ACCESSIBLE
☒ YES: RESTRICTED
☐ YES: UNRESTRICTED
☐ NO

PRESENT USE

☐ AGRICULTURE
☒ COMMERCIAL
☐ EDUCATIONAL
☐ ENTERTAINMENT
☐ GOVERNMENT
☐ INDUSTRIAL
☐ MILITARY
☒ MUSEUM
☐ PARK
☒ PRIVATE RESIDENCE
☒ RELIGIOUS
☐ SCIENTIFIC
☐ TRANSPORTATION
☐ OTHER**4 OWNER OF PROPERTY**

NAME

Multiple Ownership

STREET & NUMBER

CITY, TOWN

VICINITY OF

STATE

5 LOCATION OF LEGAL DESCRIPTIONCOURTHOUSE,
REGISTRY OF DEEDS, ETC.

Office of Recorder of Deeds, Boone County Courthouse

STREET & NUMBER

Eighth and Walnut streets

CITY, TOWN

Columbia

STATE

Missouri 65201

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

1. Missouri Historic Sites Catalogue

DATE

1963 (published)

☐ FEDERAL ☒ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR
SURVEY RECORDS

State Historical Society of Missouri, Corner, Hitt and Lowry street

CITY, TOWN

Columbia

STATE

Missouri 65201

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 6 PAGE 1

2. A Boone County Album
1971 (published)

Local survey

Committee on Historic Sites and Tours of the Columbia-Boone County
Sesquicentennial Commission, James Darrough, Chairman

Columbia, Missouri 65201

3. Missouri State Historical Survey

1973-1975

State survey

Office of Historic Preservation
Department of Natural Resources
P. O. Box 176
Jefferson City, Missouri 65101

ITEM NUMBER 11 PAGE 1

2. Mrs. M. Patricia Holmes, editor
Research Associate
Office of Historic Preservation
Department of Natural Resources
Jefferson City, Missouri 65101

Date: February 11, 1976

314/751-4096

3. Maryellen McVicker and Curtis R. Thomas, Students
Department of Art History and Archeology
University of Missouri-Columbia
Columbia, Missouri 65201

Date: 1973-1974

7 DESCRIPTION

CONDITION

☐ EXCELLENT
☐ GOOD
☒ FAIR

☐ DETERIORATED
☐ RUINS
☐ UNEXPOSED

CHECK ONE

☐ UNALTERED
☒ ALTERED

CHECK ONE

☒ ORIGINAL SITE
☐ MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Rocheport Historic District encompasses the entire town of Rocheport, Missouri, which is located at the western edge of Boone County on the north bank of the Missouri River at the confluence of Moniteau Creek. There is a central zone containing a concentration of historic structures within an area defined and restricted by the local planning and zoning ordinance adopted by the City of Rocheport January 22, 1974, and there is a peripheral zone including fewer, though none-the-less significant examples of historic structures.

The Rocheport Historic District contains some 80 architecturally or historically significant buildings. Dating from the first quarter of the nineteenth through the first quarter of the twentieth centuries, these structures reflect the history of Rocheport during its prominence.

Central Street is the main artery and the commercial focus of Rocheport. Central Street commences near Moniteau Creek, slightly above its confluence with the Missouri River and extends in a straight line southward toward the river. Other streets are oriented at right angles or parallel to Central Street. Central Street is bordered by limestone guttering, constructed by William Slade in the 1840s and described in the early history as a "model of professional construction."

The historic houses and commercial buildings are situated near the street line with the long axis parallel to the street. The structures are wood-frame, log, or brick, with wood-frame predominant in the "cottage" homes. The majority of the buildings are roofed with tin. Intrusions are one-story buildings, simple in design and about the same height as the historic structures. Six mobile homes are located in the central zone. These units were already in place at the time the zoning regulation was passed, and no others will be located there in the future. The few commercial buildings clustered along Central Street, although of later vintage, are constructed of materials and with the style which harmonize with the older structures.

The early Rocheport residents, emigrants from Virginia and Kentucky, reproduced in unpretentious form the simple, classically-derived residential architecture with which they were familiar. The earliest surviving buildings date from the 1830s and were constructed soon after the incorporation of Rocheport in 1836. In this small, fourth-class city, only a few of the buildings have street numbers. The numbers used in this report are structure inventory numbers. The 1970 United States census lists Rocheport as a city of 307 inhabitants.

The peripheral zone includes the 1892 Missouri, Kansas and Texas Railroad Tunnel (at the west edge of town, a cluster of structures--a church and several residences--associated with Rocheport's black population, at the southeast corner of town, and early structures which are in deteriorated but virtually unaltered condition at the east edge of town.

The commercial center of the Historic District borders Central Street between Second and Third streets. On the west side of the street is a block of four brick row buildings. The F. E. Bysfield Store Building (8), the northernmost row build-

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7

PAGE 1

ing, erected in the 1890s, was formerly a jewelry and hardware store and has been used more recently as an antique shop. The three buildings to the south were erected in 1924 after a disastrous fire destroyed former structures at the site. The three later buildings exhibit the same quality and color of brick and the same style as the older building in the row. Immediately to the south of the older building is the 1924 Bysfield Memorial Building (9), erected by Bysfield's wife as a memorial to him. It was formerly used as a general store, but at present is vacant. The former B. F. Dimmitt Drugstore (10) is the next building to the south. Original walnut cupboards and showcases and a stained glass decorative window remain in the building, now used as a ceramics shop.

The fourth row building, which stands at the corner of Central and Second streets, housed the Bank of Rocheport (11) until 1944. The lower walls of the old lobby were originally lined with marble. The building is restored and in use as a post office.

Across the street from the Dimmitt building is the Miriam Green Craft Shop (21), owned and operated by the Friends of Rocheport since 1968. Constructed in 1904 from handmade brick from older buildings, it was formerly used as a farm produce shop. To the south stands the former Peoples Bank of Rocheport (20), erected in 1910, and now in use as the Christian Church annex. With its splayed lintels and ornamental cornice, it is the most outstanding example of brickwork in Rocheport.

South of the Annex, across Second Street and facing west, stands the Keiser-Dimmitt House (19) (ca. 1837), the former residence of Captain John W. Keiser was enlarged by the B. F. Dimmitt family. The house was restored and a third addition was built in 1968, but it still retains its three-bay, two-story, classically-derived design. The interior features handmade brick fireplaces in three of the original rooms, the original, steep staircase in the west hall, wide board floors and chair rails.

Facing west on Central Street, south of the Keiser-Dimmitt House stands the one-story, three-bay brick William Gaw House (18). Chimneys at each end of the rectangular structure and a side porch with carved wooden pillars remain. The house was built by William Gaw, one of the original residents of Rocheport and dates from the 1830s. It was restored in 1970.

Proceeding west from the corner of the Keiser-Dimmitt House along Second Street, the pink granite Boonslick Road Marker (59), erected in 1913 by the Daughters of the American Revolution and the State of Missouri, stands along the sidewalk. East of the marker and facing north is the Dr. E. C. Chinn-Polly Gentry House (60), a two-story, frame residence with fireplaces in three rooms. An

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 2

original handmade brick outbuilding with a four-sided hip roof and a cupola remain. The property has recently been completely renovated and the outbuilding restored.

On the opposite side of Second Street, facing south, is the 1845 Christian Church (69) constructed of handmade brick laid in Flemish bond. In 1880 the original spire was replaced, and the building restored. Recessed double doors and the original etched glass windows are outstanding features.

East of the church, facing south on Second Street, is the J. H. Chambers House (60) built in 1878. The original porch has been replaced on this central pedimented, two-story, frame residence with a one-story ell in the rear.

At the corner of Columbia and Second streets, facing south, is the two-story, brick Wilcox-Barth House (67), with recessed front door, leaded sidelights, stone sills and keystone lintels. Fireplaces remain in each of the four original rooms. Two of the original rooms on the east have been removed. Built on the central hall plan, a "U"-shaped staircase with carved balusters and a slender newel post, lead to the upper story. Wide board floors remain in the original rooms. Walnut wood work and cross and Bible doors are outstanding features. Built by Rueben Elliott for Dr. George Wilcox, it was one of the first brick houses erected in Rocheport. Several north additions have given the house its present "L" plan. This house is presently in good repair.

At the corner of Lewis and Second streets, facing south, is the Grossman-Barth House (65), a one-story, frame cottage built in the 1850s by Leopold Grossman and owned in the 1860s by Moses Barth. A five-bay design, it features shuttered windows, and an entrance with sidelights and transom. It was originally a four-room house with a central hall. Before the turn of the century, one room was removed on the northwest and two rooms were added to the northeast, making the structure "L"-shaped. The house was restored in 1969.

The William Crump House (79), a two and one-half story, "L"-plan, frame structure with central pediment and ornamental scroll-saw work on the gabled roof, is located at Lewis and Third streets. Built in 1867, the structure retains its original features and is well preserved.

East of the Crump House stands the 1861 United Baptist Church of Christ (78). The cupola was replaced in the 1929 restoration by Dr. Charles Q. Chandler, Jr., Kans banker and native of Rocheport. The building is now used as the Community Hall.

At the corner of Third and Clark streets, facing north, is the W.E.T. Waddell House (77) (ca. 1840), a one-story frame cottage with recessed doorway, side lights and

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 3

closed fireplaces in two rooms. It was restored in 1970.

On the opposite side of the street, facing south, is the brick, two-story Rocheport school building (72) (1914), now in use as a trading post.

North of Third Street on Lewis Street, facing west, stands a frame ice house (44), owned by the Friends of Rocheport, a gift of Mr. and Mrs. Grover C. Young. It is lined with brick and is in excellent condition.

North of the ice house, facing west, is the Nagel-Ridgeway House (45). Built in the 1860s by the Reverend Smith, a Baptist minister, for Conrad Nagel, it was purchased in 1877 by William Ridgeway. This one and one-half story, frame house has not been altered on the interior but the original porch was replaced.

The brick Friends of Rocheport Museum (2), facing west on Moniteau Street, was the home of George Gregory, a Rocheport merchant in the 1830s and 1840s. It was purchased by the Friends of Rocheport in 1970 and restored in 1972 as the first local history museum in the county.

The United Methodist Church (30) (1901), with its fanlighted front entrance, beamed ceilings and stained glass windows, one a memorial to Moses U. Payne, is located on Columbia Street. The one and one-half story brick church contains a number of the original pews from the first Rocheport Methodist Church built in 1844.

PRESENT STATUS

Rocheport was a "dying community" until interest in its history was awakened in the 1960s when several homes there were restored. Now Rocheport's historic residences and commercial structures are being purchased and repaired by others who are also attracted to the quiet charm of this small town which is located a convenient (10 mile) distance from Columbia, a medium-sized Missouri city with the state university and a large complex of medical facilities. The unfortunate, recent loss of several examples of early Rocheport architecture should also be mentioned as indicative of the need for official recognition of what remains.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 4

INVENTORY OF HISTORIC STRUCTURES LOCATED WITHIN THE ROCHEPORT HISTORIC DISTRICT
(The numbers are structure inventory numbers plotted on the site plan.)

1. Minor-Langdon House (Moniteau Street), Antebellum, 2 original brick rooms, fireplace between rooms removed, rooms now surrounded with modern frame building.
2. George Gregory House--Friends of Rocheport Museum (Moniteau Street), 1830s, 1-story brick, with reconstructed frame addition in rear, original fireplace, brick fired on site.
3. Brady House (First Street), 1840s, small frame building with double front doors, probably used as a store along the river front.
4. Rocheport Missouri-Kansas-Texas Railroad Tunnel (west of Moniteau Street), ca. 1893, 243 feet long, only tunnel on M-K-T Railroad.
5. Mullens-Mitchell-Smith House (Moniteau Street), 1890s, salt-box style frame in poor state of repair.
6. Sexton-Haines-Koch House (Central Street), early 1900s, original home now modernized, built on site of historic Rocheport pottery, 2-story frame.
7. Grossman-Pipes-Hollon House (Central Street), 1890s, 1-story frame with later frame addition.
8. F. E. Bysfield Building (Central Street), 1880s or 1890, handmade brick, 1-story, similar in style to adjoining business buildings. Formerly a general store.
9. F. E. Bysfield Memorial Building (Central Street), early 20th century, 1-story, name "Bysfield" on front, formerly a general store.
10. B. F. Dimmitt Drugstore (Central Street), early 20th century, one-story brick, now houses a ceramic shop, interior walnut woodwork and stained-glass window.
11. Rocheport Bank--Post Office Building (Central Street), early 20th century brick, 1-story with basement, marble formerly lined walls of lobby, ornate carving over front entrance. In use as post office.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 5

12. Schnell-Welbern Store (Central Street), 1930, similar in style to brick row buildings, 1-story.
13. Burroughs Barber Shop-City Hall (Central Street), 1930, small square brick building attached to Welbern Store.
14. Doody-Graves-Walker House (Central Street), 1900s, 1-story frame with Victorian sunbursts on gables, dry-laid stone retaining wall.
15. Central Street Gutter, 1830s, limestone gutter constructed by William Slade, pioneer citizen.
16. Nicholson-McQuitty-Miller House, (Central Street), 1850s, 5-bay, covered with asphalt siding, 2-story, fireplace on north end.
17. Burroughs Tin Shop (First Street), early 1900s, located in former business district, originally a larger building, torn down and rebuilt with old materials, brick, 1-story.
18. Knox-Gaw-Slade-Byler House (Central Street), 1835, 1-story brick, 5-bay, carved porch pillars replaced in original pattern, restored, 1970.
19. Topleff-Keiser-Dimmitt-Green House (Central Street), 1830s, 3-bay, 2-story brick with later additions, 9 over 6 paned windows in original portion, 3 fireplaces, wide board floors, slender steep staircase leads from central hall, chair rails in two rooms.
20. People's Bank of Rocheport-Christian Church Annex (Central Street), 1910, ornamental brickwork, corbelled, round arch lintels in most upper story windows, belted between upper and lower stories, windows on first floor have flat brick lintels with keystones. Recessed stone front doorway with transom.
21. Miriam Green Craft Shop (Central Street), 1904, 1-story brick, central doorway with side lights and transom. Restored, 1968 by Friends of Rocheport. Built with brick from earlier buildings on the site which burned.
22. Thomas D. Pipes House (Central Street), early 1900s, three original rooms remain in this 1-story frame residence (formerly 2-story), recently "modernized."

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 6

23. Haller-Grossman-Cook House (Central Street), 1890s, 2-story rectangular frame covered with asphalt siding, L-shaped.
24. Canole-Harper-Hines House (Central Street), 1890s, 1-story frame, with 2 porches, back porch with scroll saw work, front porch with pillars.
25. Payton-Rapp-Boyd House (Columbia Street), late 1800s, 1-story frame.
26. Byers-Peeler House (Columbia Street), 1910, 2-story frame with central gable. Scroll saw work on porch.
27. Inman-Morris House (Columbia Street), 1840s, 1-story, 5-bay, symmetrical facade, frame, restored.
28. Slade-Deputy House (Columbia Street), 1840s, 1-story frame, central doorway with transom and side lights, dentiled cornice design, bay window added.
29. Rocheport United Methodist Parsonage (Columbia Street), 1896, 2-story frame, scroll saw work decorated porch, carved interior woodwork with rosette design.
30. Rocheport United Methodist Church (Columbia Street), 1901, 1 1/2-story brick, with ornamental brickwork, exposed interior walnut ceiling beams, ornate pews, memorial stained glass windows.
31. Swanstone-Murray House (Columbia Street), 1830s, log house with brick addition. In poor condition.
32. Head-Smith House (Columbia Street), 1830s, 1-story brick and frame. In poor condition.
33. Challis-Champion-Chinn-Richardson-Jackson House (Columbia Street), 1880s, original home now modernized.
34. Huntington-Wiswall-Wyatt House (Columbia Street), 1830s, 2-story, combined log and frame, covered with asphalt siding, "eyebrow windows" in 2nd story (extremely rare type in Missouri), central hall with two separate sections, south room log. According to legend a private school held there.
35. Hourigan-Jacobs House (Columbia Street), 1917, 1-story frame, now modernized.
36. Harris-Garrett House (Columbia Street), 1840s, 1-story frame with two front entrances, formerly a 2-story house, a portion of the staircase remains in the house. In poor condition.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 7

37. Rapp-Tipton House (Columbia Street), early 1900s, 1-story frame, with scroll saw ornament on porch. Retains original appearance.
38. Scobee-Gardner House (Lewis Street), 1901, retains original tin roof with fleur de lis finials, unusual construction material--concrete scored to resemble brick.
39. Matheny-Welbern House (Lewis Street), 1920s, 1 1/2 story frame with central pediment, "modernized."
40. McAllister-Champion-Rapp-Fredmeyer House (Lewis Street), 1850s, 1-story, 5-bay frame, central door with transom and side lights.
41. Hern-Shippert House (Lewis Street) 1840s, 3-bay frame covered with asphalt siding, salt box type, garage added.
42. Bysfield-Butcher House (Lewis Street), mid-19th century, some original windows "modernized."
43. Boone-Salzmann House (Lewis Street), 1880s, preserves original appearance, 2-story frame.
44. Ridgeway-Young-Friends of Rocheport Ice House (Lewis Street south of alley), 1870s, brick lined. Rare survival of a once-common dependency structure type.
45. Nagel-Ridgeway-Young House (Lewis Street), 1866, built by Baptist minister, Smith. Family home for 100 years, 1 1/2 story frame, flush siding between pilasters on first story, porch has been replaced, central gable.
46. Jones-Dodson-Corbin House (Lewis Street), late 19th century, 1-story frame with attic.
47. Champion-White-Gardner-Caldwell House (Clark Street), early 20th century, porch has been replaced.
48. Sexton-Pipes-Schnell House (Clark Street), early 20th century, 2-story, wood-frame Victorian, restored.
49. Smith-Moreau House (Clark Street), Mid-19th century, 2-story, 3-bay home, covered with asphalt siding, side lights and transom at front door, porch has been replaced.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

ROCHEPORT HISTORIC DISTRICT

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER

7

PAGE

8

50. Potts-James House (Fourth Street), late 19th century, wood-frame, rectangular plan house. Peaked lintels. Front door has been moved to gable end.
51. O'Howell-Burroughs House (Pike Street), 1850s, Greek-Revival gable molding, scroll saw, Victorian porch added, little altered example. In poor condition.
52. Jackman-Connor House (Pike Street), 1840s or 50s, 1-story frame, now in ruins.
53. Hensley-Henderson House (First Street), antebellum and much altered.
54. Jackman-McDaniel House (First Street), late 19th century rebuilt in 1930s.
55. Mount Nebo Baptist Church (Ward Street), frame, ca. 1860s, associated with local black history.
56. Mount Nebo Baptist Church Parsonage (Ward Street), post Civil War, frame, in poor condition.
57. Wilhite House (First Street), antebellum, only house in Rocheport with brick lower story and wood-frame upper story.
58. Murray-Brown House (Second Street), late 19th century, 1-story frame covered with steel siding, formerly housed telephone exchange.
59. Boonslick Road Marker (Second Street), 1913, erected by Daughters of the American Revolution to mark historic trail through Rocheport.
60. Chinn-Gentry-Hourigan House (Second Street), 1840s, fine woodwork, original fireplaces (3), staircase, original brick outhouse with hip roof and cupola. House renovated with an addition, 1975. Retains original 3-bay facade, side hall and U-shaped stairs.
61. Bysfield-Rodebaugh House (Second Street), 1912. Porch on back pilastered with paneled area under windows. Home restored 1975 with carport added.
62. Drake-Cochran-Rude Rouse House (Second Street), 1900s, frame with shingles in gables.
63. Tamy-Angell-Williams House (Second Street), antebellum, 5-bay, 2-story design, shutters removed, new siding covers cornice moldings, porch partially filled in to make a room. Side lights at front door.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 9

64. Bentley-Campbell-Kotiw House (Second Street), 1840s, 1-story, 5-bay Greek Revival design retaining more than usual original integrity.
65. Grossman-Barth-Caldwell House (Second Street), 1850s, 1-story frame, 5-bay, symmetrical design. Front porch not original. Restored, 1960s.
66. Williams-Peeler-DeHaven House (Second Street), 1850s, 1-story, frame, details of Greek Revival design survive, addition on rear.
67. Wilcox-Barth-Dew House (Second Street), 1837, first brick home in Rocheport. 2-story, 5-bay design. 2 rooms on east removed, restored 1970s with addition on north, fireplace in each of original five rooms, carved staircase, carved woodwork, wide board floors.
68. Chambers-Rapp House, (Second Street), 1878. 2-story, 5-bay frame with central gable, porch replaced.
69. Rocheport Christian Church (Second Street), 1845, one of the oldest Christian Church buildings erected by a Disciples of Christ congregation and used continuously by a Disciples of Christ congregation in the United States. Cupola changed in 1880. Brick, Flemish bond, frosted glass windows. Brick in common bond on back and sides. Double entrance.
70. Chapman-Hollon House (Third Street), 1830s, 1-story, 3-bay log with additions.
71. Campbell-Byers House (Third Street), early 1900s, 1-story frame with 1/2 story upper, front dormer.
72. Rocheport School-Friends of Rocheport Building (Third Street), 1914, 2-story brick with basement. Now used for commercial purposes.
73. Norris-Norris-Sampson-Clemens House (Third Street), 1830s, completely "modernized," formerly 2-story frame, now 1-story.
74. Brown-Liggett House (Third Street), mid-19th century, porch replaced, Gothic Revival window in front gable. 3-bay, wood-frame, clapboard siding.
75. Harold Garrett House (Third Street), antebellum, now in ruins.
76. Hill-Roby-Wood House (Third Street), 19th century, frame home covered with modern vertical boards.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 10

77. Waddell-Rucker-Burroughs-Rapp House (Third Street), 1840s, rectangular 1-story frame with fireplaces on east and west, wide board floors, restored, 1970s.
78. Community Hall (Third Street), 1861, built as Baptist Church, restored in 1929 by C. Q. Chandler as memorial to father and mother. Flemish bond brick, two entrances.
79. Crump-Prince-Haines House (Third Street), antebellum, 2-story L-shaped frame with fireplace chimneys on east and west. Gothic revival windows in attic gable ends, ornate bargeboards and eaves, well preserved.
80. Cox-Welbern-Perkins House (Moniteau Street), 1900s, 1-story frame.
81. Isidor Broaddus House (Third Street), third quarter 19th century, wood-frame covered with metal siding. Family home for about 100 years.

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
PREHISTORIC	__ ARCHEOLOGY-PREHISTORIC	__ COMMUNITY PLANNING	__ LANDSCAPE ARCHITECTURE	__ RELIGION
1400-1499	__ ARCHEOLOGY-HISTORIC	__ CONSERVATION	__ LAW	__ SCIENCE
1500-1599	__ AGRICULTURE	__ ECONOMICS	__ LITERATURE	__ SCULPTURE
1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	__ EDUCATION	<input checked="" type="checkbox"/> MILITARY	__ SOCIAL/HUMANITARIAN
1700-1799	__ ART	__ ENGINEERING	__ MUSIC	__ THEATER
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> COMMERCE	<input checked="" type="checkbox"/> EXPLORATION/SETTLEMENT	__ PHILOSOPHY	<input checked="" type="checkbox"/> TRANSPORTATION
1900-	<input checked="" type="checkbox"/> COMMUNICATIONS	<input checked="" type="checkbox"/> INDUSTRY	<input checked="" type="checkbox"/> POLITICS/GOVERNMENT	__ OTHER (SPECIFY)
		__ INVENTION		

SPECIFIC DATES 1804, 1822, 1836

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Rocheport, in Boone County, Missouri, is significant as an early nineteenth century central Missouri river town which has retained a concentration of representative examples of its early residences and commercial buildings. Situated on the Boonslick Trail, an old westward route, Rocheport figured in river, railroad and road trade. The town early produced milled lumber, bricks, leather, tobacco and ceramic. Rocheport hosted the 1840 state Whig convention and suffered at the hands of Civil War guerrillas.

The first recorded history of the site was on June 7, 1804, in the journals of the Lewis and Clark Expedition. A limestone rock covered with "uncouth paintings of animals" was noted near the mouth of the Moniteau Creek.¹ The site was included in a New Madrid grant patented to David Gray on November 13, 1822, by the United States government.² Lots were advertised for sale in 1825 and additional lots were sold in 1828 and 1832.³ Rocheport, reputedly named by a French missionary,⁴ was incorporated in 1836.

With a fine natural harbor, Rocheport grew rapidly as a boat landing and ferry crossing site in the Boonslick Country, an area which derived its name from the salt lick in Howard County, where Nathan Boone and Daniel Morgan Boone, sons of Daniel Boone, manufactured salt.⁵ Westbound travelers coming off the historic Boonslick Trail at Rocheport crossed the Missouri River there on the Rocheport ferry. In 19 Rocheport became a ferry crossing point on the National Old Trails Road.⁶

In 1835 Rocheport had eight stores, two carding machines, a steam sawmill, five brickyards, two tanyards, two ropewalks and a tobacco factory. During the year the town was considered by the state senate as the site for the location of the state university.⁷ In 1844 a pottery was established there.

The growth of Rocheport paralleled the development of Missouri River steamboat transportation. In 1849 fifty-seven steamboats made 500 landings at Rocheport.⁸ Nine years previously, the Whigs held their state convention at Rocheport. On June 18, 1840, several thousand delegates came by steamboat, carriage, wagon, and horseback. The St. Louis delegates, arriving on the Rienzi and the Platte, two of the largest steamboats on the river, brought bands, two live eagles and the replica of a log cabin. Among the banners carried by county delegations in the mile-long parade was one painted by George Caleb Bingham, famous Missouri artist. Bingham and Fletcher Webster, son of Daniel Webster, were among the speakers at the convention.⁹

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

ROCHEPORT HISTORIC DISTRICT

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 1

By 1860 Rocheport had a population of 753, which included 130 slaves.¹⁰ Predominantly Southern in sympathy, both Union soldiers and "Wild Bill" Anderson's Confederate guerrillas raided Rocheport during the Civil War.¹¹ One of Rocheport's principal business blocks and the school building were burned.

Rocheport revived after the war. Before the turn of the century business establishments thrived, banks were organized, newspapers were published and a railroad was built. In 1870 Colonel R. A. Caskie engaged in the tobacco trade and for several years shipped 1,000 hogsheads of tobacco to England and Scotland annually.¹² One of the first rural telephone lines in Missouri was built from Rocheport to Columbia Missouri, in 1878.¹³ In 1875 the Mattie Belle, a 350-ton boat, was constructed at Rocheport.¹⁴ The ferry, in later years a double-decked, steam-powered boat, carried passengers until 1922.¹⁵ The Missouri, Kansas and Texas Railroad was built through the town in 1892 and freight traffic has continued on the line to the present day. The picturesque railroad tunnel, the only tunnel on the Missouri, Kansas and Texas, is located at the southwest edge of the city.¹⁶

Rocheport suffered disastrous fires in the business district in 1892 and 1922.¹⁷ Frequent flooding of the Missouri River caused the removal of business houses from the riverfront to the higher location on Central Street. Antebellum residences and two church buildings, left intact from the ravages of the Civil War and built away from the river, still stand.

The decline of steamboat transportation and the construction of modern highways which bypassed Rocheport resulted in the town's decline. From a population of 823 in 1870, the number of inhabitants decreased to 593 in 1900.¹⁸ Rocheport remained a neglected town for many years with its century-old buildings untouched. In 1967 a group of interested citizens organized the Friends of Rocheport for the purpose of preservation and restoration of historic structures and since that time the work has progressed steadily. The annual Friends Fest, sponsored in June by the Friends of Rocheport, brings hundreds of visitors to Rocheport. The Rocheport Museum and the Rocheport Craft Shop, both owned and restored by the Friends of Rocheport, are visited by more than 2,000 persons each year. Five antique shops, located there, are all added attractions.

Two Missourians, noted in the history of the state, were Rocheport residents. Moses U. Payne, known as "Missouri's Millionaire Minister," established a store in Rocheport in 1841. A lay minister, he frequently preached at the Rocheport Methodist Church.¹⁹ Because of his generous gifts, the former Howard-Payne College at Fayette, in Howard County, Missouri, was named for him. The present William Woods College at Fulton, Missouri, was named for William S. Woods, a Rocheport banker in the 1870s. Woods organized the Rocheport Savings Bank in 1869 and later organized

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 2

a Kansas City bank which became the Kansas City Trust Company.²⁰ The Rocheport Christian Church stands today as the oldest Christian Church building in continuous use west of the Mississippi River.²¹

Dr. George Wilcox, original owner-builder of the Wilcox-Barth House, was reputed to be the first physician in Boone County. For many years the house was occupied by Moses Barth, a Rocheport merchant who founded a commercial empire in Central Missouri. A Barth store is still operating in Columbia, Missouri.

Captain John W. Keiser was the owner and master of several steamboats and the founder of the first paper mill west of the Mississippi River.

The B. F. Dimmitt Drugstore was a favorite stopping place for travelers on the National Old Trails Road as fame spread of the soda fountain where he served free "nectar," a homemade carbonated drink.

FOOTNOTES

1. Paul Allen, ed., History of the Expedition Under the Command of Captains Lewis and Clark to the Sources of the Missouri (Philadelphia, 1814), I, 12.
St. Louis Tri-Weekly Missouri Republican, October 28, 1863.
2. History of Boone County, Missouri, (St. Louis, Mo.: Western Historical Company, 1882), 998.
3. Franklin Missouri Intelligencer, September 2, 1825.
4. David W. Eaton, How Missouri Counties, Towns and Streams Were Named (Columbia, Missouri: The State Historical Society of Missouri, 1916), 212-213.
5. Floyd C. Shoemaker, Missouri and Missourians (Chicago, 1943), I, 587.
6. University Missourian (Columbia), October 2, 1911.
7. History of Boone County, Missouri, op. cit., 1000-1001.
Columbia Missouri Intelligencer, March 7, 1835.
8. History of Boone County, Missouri, op. cit., 1000.
9. Ibid., 1000.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 3

10. Joseph C. Kennedy, Population of the United States in 1860; Compiled from the Original Returns of the Eighth Census (Washington, D. C., 1864), 288.
11. Columbia Missouri Statesman, July 15, 1864; July 22, 1864; Liberty Tribune, July 29, 1864.
12. History of Boone County, Missouri, op. cit., 1003.
13. Columbia Herald, August 28, 1878.
14. Missouri Historical Review, XXI, (April, 1927), 475.
15. Columbia Missourian, October 11, 1921; June 8, 1922.
16. Columbia Missouri Statesman, March 2, 1892; Boonville Weekly Advertiser, March 3, 1893; Letter from M. Ritchey Cring, vice president Public Relations, Missouri-Kansas-Texas Railroad Company, February 6, 1971.
17. Columbia Missouri Statesman, June 18, 1892; Columbia Missourian, January 11, 1922.
18. The Statistics of the Population of the United States . . . Compiled from the Original Returns of the Ninth Census (Washington, D. C.), 187; Census Reports Twelfth Census of the United States Taken in the Year 1900 (Washington, D. C., 1901), 461.
19. John C. Crighton, "Moses U. Payne was Extremely Successful Pioneer Merchant," Columbia Daily Tribune, January 13, 1974; January 27, 1974.
20. Griffith A. Hamlin, In Faith and History: The Story of William Woods College (St. Louis, 1965), 81. Columbia Herald, December 2, 1904.
21. The Christian Standard, Vol. 50 (August 21, 1915), 1526. The Christian, Vol. 16 (March 28, 1878), 2. Disciplianas, Vol. 10 (October, 1950). The Christian Evangelist, Vol. 66 (August 1, 1929), 1011. These references were included in a letter from Helen P. Bracey, assistant librarian of the Disciples of Christ Historical Society to Mrs. George C. Harper, Rocheport, Missouri, February 28, 1974.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

1. Allen, Paul, ed. History of the Expedition Under the Command of Captains Lewis and Clark to the Sources of the Missouri 2 vols. Philadelphia, 1814.
2. Boonville Weekly Advertiser, March 3, 1893.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY Approximately 147 acres.

UTM REFERENCES

A	<input type="text"/>	<input type="text"/>	<input type="text"/>	B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	ZONE	EASTING	NORTHING		ZONE	EASTING	NORTHING
C	<input type="text"/>	<input type="text"/>	<input type="text"/>	D	<input type="text"/>	<input type="text"/>	<input type="text"/>

VERBAL BOUNDARY DESCRIPTION

The boundaries of the Rocheport Historic District correspond to the city limits of the City of Rocheport, Missouri, with the exception that there is additional area included to the west to encompass the MKT railroad tunnel. The western boundary proceeds southward from the northwest corner of the town of Rocheport, approximately 1625 feet, thence westward approximately 875 feet, thence southward approximately 187 feet, thence eastward approximately 875 feet to the western boundary of the Rocheport city limits.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
STATE	CODE	COUNTY	CODE

11 FORM PREPARED BY

NAME / TITLE	Mrs. Dorothy J. Caldwell, Former Associate Editor, Missouri
ORGANIZATION	1. <u>Historical Review, State Historical Society of Missouri, Columbia,</u>
	Friends of Rocheport
STREET & NUMBER	Moniteau Street
CITY OR TOWN	Rocheport

DATE	March 27, 1975
TELEPHONE	314-698-2444
STATE	Missouri 65279

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL ☐ STATE ☐ LOCAL ☐

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

TITLE	Director, Department of Natural Resources and State Historic Preservation Officer	DATE
-------	---	------

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

DATE

ATTEST: DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION

DATE

KEEPER OF THE NATIONAL REGISTER

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 1

3. Bracey, Helen P., assistant librarian of the Disciples of Christ Historical Society, letter to Mrs. George C. Harper, Rocheport, Missouri, February 28, 1974.
4. Caldwell, Dorothy J. "Rocheport, River Town," A Boone County Album. Columbia, Missouri: Kelly Press, 1971.
5. _____ and Mrs. George Russell, (eds.). Rocheport, River Town of the Boonslick Country. Columbia, Missouri: Kelly Press, 1968.
6. Census Reports: Twelfth Census of the United States Taken in the Year 1900. Washington, D. C., 1901.
7. The Christian, Vol. 16, March 28, 1878.
8. The Christian Evangelist, Vol. 66, August 1, 1929.
9. The Christian Standard, Vol. 50, August 21, 1915.
10. Columbia Herald, August 28, 1878.
11. _____, December 2, 1904.
12. Columbia Missouri Intelligencer, March 7, 1835.
13. Columbia Missouri Statesman, January 28, 1870.
14. _____, March 2, 1892.
15. _____, June 18, 1892.
16. _____, July 15, 1864.
17. _____, July 22, 1864.
18. Columbia Missourian, October 11, 1921.
19. _____, January 11, 1922.
20. _____, June 8, 1922.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 2

21. Crighton, John C. "Moses U. Payne was Extremely Successful Pioneer Merchant," Columbia Daily Tribune, January 13, 1974; January 27, 1974.
22. Cring, M. Ritchey, vice president, public relations, Missouri-Kansas-Texas Railroad Company, letter to Mrs. Dorothy J. Caldwell, February 6, 1971.
23. Disciplianas, Vol. 10, October, 1950.
24. Eaton, David W. How Missouri Counties, Towns and Streams Were Named. Columbia, Missouri: The State Historical Society of Missouri, 1916.
25. Franklin Missouri Intelligencer, September 2, 1825.
26. Hamlin, Griffith A. In Faith and History: The Story of William Woods College. St. Louis, Missouri: Printed as a private edition, 1965.
27. History of Boone County, Missouri. St. Louis, Missouri: Western Historical Company, 1882.
28. Kennedy, Joseph C. Population of the United States in 1860; Compiled from the Original Returns of the Eighth Census Washington, D. C., 1864.
29. Liberty Tribune, July 29, 1864.
30. Missouri Historical Review, xxi, April, 1927, 475.
31. St. Louis Tri-Weekly Missouri Republican, October 28, 1863.
32. Shoemaker, Floyd C. Missouri and Missourians. 5 vols., Chicago: The Lewis Publishing Company, 1943.
33. The Statistics of the Population of the United States . . . Compiled from the Original Returns of the Ninth Census. Washington, D. C., [1870].
34. University Missourian (Columbia), October 2, 1911.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

ROCHEPORT HISTORIC DISTRICT

CONTINUATION SHEET

ITEM NUMBER 10

PAGE 1

Thence southeasterly along the midline of the Moniteau Creek to the point of intersection with the eastern city limit line of Rocheport at the confluence of Moniteau Creek and the Missouri River.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM**

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- ENCLOSE WITH MAP

1 NAME

HISTORIC

Rocheport

AND/OR COMMON

Rocheport Historic District

2 LOCATION

CITY, TOWN

Rocheport

____ VICINITY OF

COUNTY

Boone

STATE Missouri

3 MAP REFERENCE

SOURCE

Missouri State Highway Department

SCALE

Not to Scale

DATE 1959

4 REQUIREMENTS

TO BE INCLUDED ON ALL MAPS

1. PROPERTY BOUNDARIES
2. NORTH ARROW
3. UTM REFERENCES

Map No. 4--demonstrating photographic views.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- ENCLOSE WITH MAP

1 NAME

HISTORIC Rocheport

AND/OR COMMON Rocheport Historic District

2 LOCATION

CITY, TOWN Rocheport VICINITY OF COUNTY Boone STATE Missouri

3 MAP REFERENCE

SOURCE United States Geological Survey Rocheport Quadrangle

SCALE 1:24000 DATE 1952

4 REQUIREMENTS

TO BE INCLUDED ON ALL MAPS

1. PROPERTY BOUNDARIES
2. NORTH ARROW
3. UTM REFERENCES

Map No. 1

GLASGOW 25 MI.
FAYETTE 12 MI.


STATE OF MISSOURI
GEOLOGICAL SURVEY AND WATER RESOURCES
EDWARD L. CLARK, STATE GEOLOGIST

35'

(HILLDALE)

R. 15 W. R. 14 W.


32'30"



ROCHEPORT HISTORIC DISTRICT
Rocheport, Missouri "Rocheport, Mo."
Quadrangle USGS 7.5' 1952

UTM REFERENCES

A 15/538249/4314706 C 15/537132/4314179
B 15/538228/4313624 D 15/537433/4314732



ROCHEPORT HISTORIC REGISTER

#254

COUNTY-

Boone

LOCATION-

Rocheport, Missouri 65279

OWNER:
ADDRESS:

Multiple ownership

DATE APPROVED BY A.C.

03-05-76

DATE SENT TO JEFF. CITY

03-30-76

DATE SENT TO B.C.

04-08-76

DATE OF REC. IN D.C.

04-13-76


DATE PLACED ON NATIONAL REGISTER:

10-08-76

DATE AWARDED CERTIFICATE
(AND PRESENTER)

DATE FILE REVIEWED

Rochepoort, in Boone County, Missouri, is significant as an early nineteenth century settlement in Boone County, Missouri, which has retained a concentration of pre-1850 architecture. Its early residences and commercial buildings, situated on the Boone River trail, an old westward route, Rochepoort figured in river, road and wagon trade. The town early produced milled lumber, bricks, leather, tobacco and cereals. Rochepoort hosted the 1840 state whig convention and suffered at the hands of Civil War guerrillas.




BOONSLICK
ANTIQUES

2 BLOCKS
EAST



























KODAK 5052 TMX

1

2 KODAK 5052 TMX

3

KODAK 5052 TMX

4

KODAK 5052 TMX

5



0A

1

KODAK 5052 TMX

6

1A

2

KODAK 5052 TMX

7

2A

3

KODAK 5052 TMX

8

3A

4

KODAK 5052 TMX

9

4A

5

KODAK 5052 TMX

10



5A

6

KODAK 5052 TMX

11

6A

7

KODAK 5052 TMX

12

7A

8

KODAK 5052 TMX

13

8A

9

KODAK 5052 TMX

14

9A

10

KODAK 5052 TMX

15



10A

11

KODAK 5052 TMX

16

11A

12

KODAK 5052 TMX

17

12A

13

KODAK 5052 TMX

18

13A

14

KODAK 5052 TMX

19

14A

15

KODAK 5052 TMX

20



15A

16

KODAK 5052 TMX

21

16A

17

KODAK 5052 TMX

22

17A

18

KODAK 5052 TMX

23

18A

19

KODAK 5052 TMX

24

19A

20

KODAK 5052 TMX

25



20A

21

KODAK 5052 TMX

26

21A

22

KODAK 5052 TMX

27

22A

23

KODAK 5052 TMX

28

23A

24

KODAK 5052 TMX

29

24A

25

KODAK 5052 TMX

30